

Item	Item Description	Qty	Unit	Unit Price	Total
1020.00	BONDS AND INSURANCE	1	LS	\$ 65,900.00	\$ 65,900.00
1020.01	CONTRACTOR TESTING	1	LS	\$ 91,400.00	\$ 91,400.00
1020.02	CONSTRUCTION STAKING	1	LS	\$ 171,100.00	\$ 171,100.00
1020.03	SURVEY MONUMENTATION	1	LS	\$ 41,200.00	\$ 41,200.00
1030	MOBILIZATION	1	LS	\$ 287,900.00	\$ 287,900.00
1030.01	FIELD OFFICE	1	LS	\$ 82,300.00	\$ 82,300.00
1035	FORCE ACCOUNT	1	LS	\$ 932,000.00	\$ 932,000.00
1050	CONSTRUCTION TRAFFIC CONTROL/SITE SAFETY	1	LS	\$ 175,800.00	\$ 175,800.00
1050.01	FLAGGING	7500	HR	\$ 50.00	\$ 375,000.00
1050.02	PILOT CAR WITH DRIVER	2000	HR	\$ 94.20	\$ 188,400.00
1050.03	VARIABLE MESSAGE SIGN PANEL	6	EA	\$ 3,100.00	\$ 18,600.00
1050.04	TEMPORARY TRAFFIC SIGNALS	320	DAY	\$ 155.00	\$ 49,600.00
1563	STORMWATER MANAGEMENT & EROSION CONTROL	1	LS	\$ 95,800.00	\$ 95,800.00
2050	REMOVAL OF MAILBOXES	62	EA	\$ 554.00	\$ 34,348.00
2050.01	REMOVAL OF PIPE [CMP]	2067	LF	\$ 11.60	\$ 23,977.20
2050.02	REMOVAL OF PIPE [RCP]	70	LF	\$ 9.15	\$ 640.50
2050.03	REMOVAL OF FES [RCP]	3	EA	\$ 1,260.00	\$ 3,780.00
2050.04	REMOVAL OF FENCE	4772	LF	\$ 1.40	\$ 6,680.80
2050.05	REMOVAL OF CONCRETE APPROACH	934	SF	\$ 3.00	\$ 2,802.00
2050.06	REMOVAL OF SIGN & POST	22	EA	\$ 128.00	\$ 2,816.00
2210	UNCLASSIFIED EXCAVATION	34181	CY	\$ 17.60	\$ 601,585.60
2210.01	UNCLASSIFIED EXCAVATION (HAUL OFF)	10499	CY	\$ 4.75	\$ 49,870.25
2210.02	MUCK EXCAVATION	3000	CY	\$ 17.00	\$ 51,000.00
2210.03	ROCK EXCAVATION	2000	CY	\$ 10.75	\$ 21,500.00
2211.01	TEMPORARY CONSTRUCTION ROAD AND MAINTENANCE	1	LS	\$ 53,000.00	\$ 53,000.00
2231	CRUSHED BASE - GRADING 'W'	39383	TON	\$ 33.10	\$ 1,303,577.30
2273.01	RIPRAP D50=12"	90	CY	\$ 288.00	\$ 25,920.00
2280	TOPSOIL STRIPPING - 4"	18613	CY	\$ 4.45	\$ 82,827.85
2280.01	TOPSOIL PLACING - 4"	18613	CY	\$ 4.45	\$ 82,827.85
2510	PORTLAND CEMENT TREATED SUBBASE - 5% APPLICATION RATE	166028	SY	\$ 8.60	\$ 1,427,840.80
2512	PLANT MIX PAVEMENT (TYPE II) GRADING - 1/2" NMAS APPROACHES - 3"	749	TON	\$ 127.00	\$ 95,123.00
2512.02	PLANT MIX PAVEMENT (TYPE II) GRADING - 3/4" NMAS - 2"	22009	TON	\$ 94.10	\$ 2,071,046.90
2512.03	PLANT MIX PAVEMENT (TYPE II) GRADING - 1/2" NMAS - 2"	20508	TON	\$ 94.80	\$ 1,944,158.40
2570.01	ADJUST WATER VALVE TO FINISH GRADE (W / CONCRETE COLLAR)	5	EA	\$ 886.00	\$ 4,430.00
2725.01	STORM SEWER CMP [APPROACHES] - 15"	700	LF	\$ 109.00	\$ 76,300.00
2725.02	STORM SEWER CMP [APPROACHES] - 18"	420	LF	\$ 118.00	\$ 49,560.00
2725.03	STORM SEWER CMP [APPROACHES] - 24"	28	LF	\$ 135.00	\$ 3,780.00
2725.04	STORM SEWER CMP - 18"	508	LF	\$ 137.00	\$ 69,596.00
2725.05	STORM SEWER CMP - 24"	178	LF	\$ 154.00	\$ 27,412.00
2725.06	STORM SEWER CMP - 30"	140	LF	\$ 168.00	\$ 23,520.00
2725.07	STORM SEWER CMP - 48"	138	LF	\$ 215.00	\$ 29,670.00
2725.08	STORM SEWER RCP - 18" (CLASS IV)	144	LF	\$ 130.00	\$ 18,720.00
2725.09	STORM SEWER RCP - 24" (CLASS IV)	74	LF	\$ 156.00	\$ 11,544.00
2725.1	STORM SEWER RCP - 36" (CLASS IV)	240	LF	\$ 252.00	\$ 60,480.00
2725.11	F.E.S. CMP [APPROACHES] - 15"	30	EA	\$ 957.00	\$ 28,710.00
2725.12	F.E.S. CMP [APPROACHES] - 18"	20	EA	\$ 991.00	\$ 19,820.00
2725.13	F.E.S. CMP [APPROACHES] - 24"	2	EA	\$ 1,190.00	\$ 2,380.00
2725.14	F.E.S. CMP - 18"	16	EA	\$ 991.00	\$ 15,856.00
2725.15	F.E.S. CMP - 24"	4	EA	\$ 1,190.00	\$ 4,760.00
2725.16	F.E.S. CMP - 30"	4	EA	\$ 1,610.00	\$ 6,440.00
2725.17	F.E.S. CMP - 48"	4	EA	\$ 2,440.00	\$ 9,760.00
2725.18	F.E.S. RCP - 18" (CLASS IV)	6	EA	\$ 1,220.00	\$ 7,320.00
2725.19	F.E.S. RCP - 24" (CLASS IV)	3	EA	\$ 1,270.00	\$ 3,810.00
2725.2	F.E.S. RCP - 36" (CLASS IV)	10	EA	\$ 2,880.00	\$ 28,800.00
2805	ALUMINUM SIGN PANEL	165.75	SF	\$ 57.60	\$ 9,547.20
2805.01	SIGN POSTS 2"x2" 12 GAUGE TYPE I (TELSPAR)	19	EA	\$ 978.00	\$ 18,582.00
2895	SOIL RETENTION BLANKET	3000	SY	\$ 3.05	\$ 9,150.00
2900	REVEG. SEEDING AND MULCHING (DRYLAND SEED MIX)	48	ACRE	\$ 1,370.00	\$ 65,760.00
3340	4" CONCRETE MAILBOX PAD	192	SF	\$ 31.80	\$ 6,105.60
3340.01	6" CONCRETE APPROACH	679	SF	\$ 31.80	\$ 21,592.20
4000	PAVEMENT STRIPING - 4" SOLID WHITE	396	GAL	\$ 83.10	\$ 32,907.60
4000.01	PAVEMENT STRIPING - 4" SOLID YELLOW	131	GAL	\$ 83.10	\$ 10,886.10
4000.02	PAVEMENT STRIPING - 4" DASHED YELLOW	40	GAL	\$ 83.10	\$ 3,324.00
4000	PAVEMENT STRIPING - 4" SOLID WHITE (TEMPORARY)	396	GAL	\$ 83.10	\$ 32,907.60
4000.02	PAVEMENT STRIPING - 4" DASHED YELLOW (TEMPORARY)	50	GAL	\$ 83.10	\$ 4,155.00
4000.03	PREFORMED THERMOPLASTIC STOP BAR	72	SF	\$ 23.10	\$ 1,663.20
4000.04	DELINEATOR - WHITE	347	EA	\$ 75.30	\$ 26,129.10
4000.05	DELINEATOR - RED	92	EA	\$ 46.50	\$ 4,278.00
4000.06	DELINEATOR - YELLOW	84	EA	\$ 75.30	\$ 6,325.20
4000.07	RUMBLE STRIP	4	EA	\$ 2,770.00	\$ 11,080.00
6000	TEMPORARY FENCE (INSTALL & REMOVAL)	4742	LF	\$ 3.05	\$ 14,463.10
6000.01	48" 4 STR BARDED WIRE AND METAL POST	2197	LF	\$ 3.90	\$ 8,568.30
6000.02	48" 5 STR BARDED WIRE AND WOOD POST	160	LF	\$ 4.40	\$ 704.00
6000.03	48" 5 STR BARDED WIRE SPECIAL 1	1210	LF	\$ 5.00	\$ 6,050.00
6000.04	48" 4 STR BARDED WIRE SPECIAL 2	1205	LF	\$ 4.85	\$ 5,844.25
6000.05	BRACE PANELS	48	EA	\$ 328.00	\$ 15,744.00
6740	MAILBOX CLUSTER TYPE 1	1	EA	\$ 5,470.00	\$ 5,470.00
6740.01	MAILBOX CLUSTER TYPE 2	6	EA	\$ 5,460.00	\$ 32,760.00
6740.02	PARCEL LOCKER	5	EA	\$ 5,400.00	\$ 27,000.00
BASE BID SUBTOTAL					\$ 11,343,986.90
BID ALTERNATE 1 - CEMENT TREAT GRAVEL ROAD SECTION					
2210.01	UNCLASSIFIED EXCAVATION (HAUL OFF) (CREDIT)	-2150	CY	\$ 4.75	\$ (10,212.50)
2231	CRUSHED BASE - GRADING 'W' - 3" (CREDIT)	-5069	TON	\$ 31.50	\$ (159,673.50)
2510	PORTLAND CEMENT TREATED SUBBASE - 5% APPLICATION RATE	27524	SY	\$ 8.95	\$ 246,339.80
BID ALTERNATE 1 SUBTOTAL					\$ 76,453.80
TOTAL BASE + ALT 1					\$ 11,420,440.70