

LARAMIE COUNTY CLERK
BOARD OF COUNTY COMMISSIONERS
AGENDA ITEM PROCESSING FORM

1. DATE OF PROPOSED ACTION: May 2, 2017

2. AGENDA ITEM: Appointments Bids/Purchases Claims
 Contracts/agreements/leases Grants Land Use: Variances/Board App/Plats
 Proclamations Public Hearings/Rules & Reg's Reports & Public Petitions
 Resolutions Other

3. DEPARTMENT: Public Works

APPLICANT: Laramie County Public Works AGENT: Rob Geringer

4. DESCRIPTION: Change order No. 1 for the Water Systems Improvements and RV Park between Rocky Mountain Sand & Gravel, LLC and Laramie County. Adding an additional \$73,213.46 to the original contract amount of \$537,692. Agenda Item - 17040413

Amount\$ 73,213.46 From: _____ To: _____

5. DOCUMENTATION: 3 Original

RECEIVED AND APPROVED AS
TO FORM ONLY BY THE
LARAMIE COUNTY ATTORNEY

Clerks Use Only:

Commissioners

Ash _____
Heath _____
Holmes _____
Kailey _____
Thompson _____

Signatures

Co Attny _____
Assist Co Attny _____
Grants Manager _____
Outside Agency _____

Action _____

Postponed/Tabled _____

Construction Change Order No. I

Project: Water System Improvements and RV Park
Engineer: BenchMark Engineers, P.C.
Owner: Laramie County, Wyoming and Laramie County Fair
Contractor: Rocky Mountain Sand & Gravel, LLC
Location: Archer Complex

Rocky Mountain Sand & Gravel, LLC is hereby directed to proceed with the following changes:

- Yard hydrants shall be Woodford S4H, or approved equal, at all locations, rather than modified frost-free hydrants.
- Replace the electrical work with the designs shown on the revised sheets dated 4-3-17. This work includes a new location for a Pad Mount Transformer by High West Energy. High West Energy will provide CTs and locate the meter at the transformer. A new Panel B and mounting bracket shall be placed northwest of the proposed dumpster area to feed the 20 RV sites west of the access road. In the main switchboard delete nine (9) 100/2 breakers and two (2) 701/2 breakers which will now be located in Panel B. Add an additional 400/3 breaker and feeder for Panel B. Provide a revised cost estimate for the associated work.
- The prices included in the original bid for item 52 (base bid) and Add Alternate A will be removed.
- The location for the Pad Mount Transformer by High West Energy has been staked, the contractor shall coordinate with High West Energy and the engineer to verify the locations of electrical components will not conflict with other proposed improvements.


The revised work will be measured and paid for as follows:

Item No.	Description	Unit	Quantity	Unit Price	Total Cost
44	Yard Hydrant, Frost-Free, modified	EA	-23	\$ 657.00	- \$ 15,111.00
52	Misc. Electrical	LS	-1	\$ 107,525.00	- \$ 107,525.00
61	Misc. Electrical, Add Alternate rough-in	LS	-1	\$ 22,250.00	- \$ 22,250.00
62	Yard Hydrant, Woodford S4H	EA	23	\$ 1,215.00	\$ 27,945.00
63	1600 Amp Switchboard	EA	1	\$ 31,107.50	\$ 31,107.50
64	1600 Amp Feeder	LF	50	\$ 431.25	\$ 21,562.50
65	400 Amp Feeder	LF	150	\$ 87.94	\$ 13,191.00
66	400 Amp Panelboard B	LS	1	\$ 2,760.00	\$ 2,760.00
67	20 RV Pedestals	EA	20	\$ 573.85	\$ 11,477.00

68	18 Pedestal Feeders	EA	18	\$ 2,266.00	\$ 40,788.00
69	NEMA 3R Panel A	LS	1	\$ 1,745.70	\$ 1,745.70
70	400 Amp Quick Disconnect	EA	3	\$ 9,932.50	\$ 29,797.50
71	400 Amp Feeder	LF	300	\$ 84.19	\$ 25,257.00
72	New 3" C Spare	LF	100	\$ 16.73	\$ 1,673.00
73	¾" x 10 Ground Rods	EA	4	\$ 117.19	\$ 468.76
74	#6 CU Ground	LF	50	\$ 4.13	\$ 206.50
75	Mounting Racks	EA	4	\$ 2,530.00	\$ 10,120.00

Total: \$ 73,213.46

Three copies of this work directive are to be signed by the following parties. Once all three are signed by each party, one copy shall be provided to each.

Issued by:  4/25/17
 BenchMark Engineers, P.C., Project Engineer Date

Accepted by:  4-25-17
 Rocky Mountain Sand & Gravel, Contractor Date

Approved by: _____
 Laramie County Representative Date Attest