

LARAMIE COUNTY PLANNING & DEVELOPMENT DEPARTMENT

Planning • Building

MEMORANDUM

TO: Laramie County Board of Commissioners

FROM: Sonny M. Keen, Associate Planner

DATE: February 18th, 2025

TITLE: CORRECTED MOTION to attach the PUD documents to the resolution for the

Zone Change from LU – Land Use to PUD – Planned Unit Development for Tracts 1-4, Terry Ranch Business Park and Lot 1, Block 1, Terry Park, Laramie County,

WY.

EXECUTIVE SUMMARY

On March 19th, 2024, Resolution Number 240319-26, was originally approved by the BOCC however the PUD rules document was not attached as an exhibit. Another motion is necessary to correct the oversite and add the PUD rules document to the zone change resolution.

RECOMMENDATION and FINDINGS

Based on evidence provided, staff finds that:

- **a.** This application does meet the criteria for a zone map amendment pursuant to section 1-2-103 (b) of the Laramie County Land Use Regulations
- **b.** The proposed change in zone district is in conformance with the requirements of section 4-2-112 of the Laramie County Land Use Regulations.

and that the Board may approve a Zone Change from LU – Land Use to PUD – Planned Unit Development for Tracts 1-4, Terry Ranch Business Park and Lot 1, Block 1, Terry Park, Laramie County, WY, with no conditions.

PROPOSED MOTION

I move to approve the "TERRY RANCH BUSINESS PARK PUD", for Tracts 1 to 4, Terry Ranch Business Park, and Lot 1, Block 1, Terry Park, as shown on exhibit "B" attached.

ATTACHMENTS

Attachment 1: Resolution

Attachment 2: Zone Change Map – Exhibit A

Attachment 3: PUD rules – Exhibit B

RESOLUTION NO.	
RESOLUTION NO.	

A RESOLUTION TO APPROVE A CHANGE IN ZONE DISTRICT FROM LU – LAND USE TO PUD – PLANNED UNIT DEVELOPMENT FOR TRACTS 1-4, TERRY RANCH BUSINESS PARK AND LOT 1, BLOCK 1, TERRY PARK, LARAMIE COUNTY, WY.

WHEREAS, Wyoming State Statutes §18-5-201 to 18-5-208; §18-5-301 to 18-5-315 authorize Laramie County, in promoting the public health, safety, morals and general welfare of the county, to regulate the use of land through zoning in unincorporated Laramie County; and

WHEREAS, the Laramie County Board of Commissioners previously adopted the Laramie County Land Use Regulations; and

WHEREAS, the proposed zone change is in conformance with the requirements of section 1-2-103(b) of the Laramie County Land Use Regulations; and

WHEREAS, the proposed zone change is in conformance with the requirements of section 4-2-112 of the Laramie County Land Use Regulations.


NOW THEREFORE BE IT RESOLVED BY THE GOVERNING BODY OF LARAMIE COUNTY, WYOMING, as follows:


The Laramie County Board of Commissioners finds that:

- This application meets the criteria for a zone map amendment pursuant to section 1-2-103 (b) of the Laramie County Land Use Regulations.
- **b.** The proposed change in zone district is in conformance with the requirements of section 4-2-112 of the Laramie County Land Use Regulations.

And the Board approves a Zone Change from LU – Land Use to PUD – Planned Unit Development for Tracts 1-4, Terry Ranch Business Park and Lot 1, Block 1, Terry Park, Laramie County, WY, and adopt the findings of fact a and b of the staff report as well as the attached 'Exhibit A' – Zone Change Map, and 'Exhibit B,' the Specific Regulations for the Planned Unit Development – PUD.

PRESENTED, READ AND ADOPTED THIS DAY OF				
, 2025.				
	LARAMIE COUNTY BOARD OF COMMISSIONERS			
	Gunnar Malm, Chairman			
ATTEST:				
Debra K. Lee, Laramie County Clerk				
Reviewed and approved as to form:				
Laramie County Attorney's Office	_			





VICINITY MAP

NOT TO SCALE

- 1. LOT 1 BLOCK 1, TERRY PARK HAS THE FOLLOWING STREET ADDRESS: 1961 US HWY 85 CHEYENNE, WY 82009
- 2. TERRY PARK AND TERRY RANCH BUSINESS PARK ARE SITUATED SOUTH OF THE EFFECTIVE AREA FOR SPECIFIC ZONE DISTRICT REGULATIONS. THE SITE IS SITUATED SOUTH OF THE TOWNSHIP LINE BETWEEN 12 AND 13 NORTH. THEREFORE ALL OF TERRY PARK AND TERRY RANCH BUSINESS PARK ARE CONSIDERED TO HAVE EXISTING ZONE
- 3. TERRY RANCH BUSINESS PARK SUBDIVISIONS CAN BE FOUND AT THE COUNTY RECORDS OFFICE, BOOK 13 PAGE 18
- 4. TERRY PARK SUBDIVISION CAN BE FOUND AT THE COUNTY RECORDS OFFICE, BOOK 7 PAGE 101

LOT 1 BLOCK 1, TERRY PARK TRACT 1, TERRY RANCH BUSINESS PARK TRACT 2, TERRY RANCH BUSINESS PARK TRACT 3, TERRY RANCH BUSINESS PARK TRACT 4, TERRY RANCH BUSINESS PARK

	LINE TABLE					
LINE#	BEARING	DISTANCE				
L1	N11'55'45"E	221.51				
L2	N2678'44"E	39.44				
L3	S63'00'59"E	49.83				
L4	N26'37'16"E	286.13				
L5	N43'29'35"W	380.22				
L6	N52'26'15"W	141.42				
L7	S52°26'15"E	141.42				
L8	S43'29'35"E	380.21				

CURVE TABLE						
CURVE#	ARC LENGTH	RADIUS	DELTA ANGLE	CHORD BEARING	CHORD LENGTH	
C1	339.64	4132.32	4*42'33"	S49°56'00"E	339.54	
C2	233.43	460.00	29*04'32"	N58°01'51"W	230.94	
С3	112.51	540.00	11°56'14"	N66°36'00"W	112.30	
C4	77.22	540.00	8"11'37"	N56°32'04"W	77.16	
C5	141.75	60.00	135°21'53"	N32°56'41"W	111.01	
C6	147.67	60.00	141*00'53"	S74°45'19"E	113.12	
C7	60.32	460.00	7*30'45"	S56"11'38"E	60.27	
С8	101.31	460.00	12*37'06"	S66"15'34"E	101.10	
С9	274.03	540.00	29°04'32"	S58°01'51"E	271.10	

ENGINEERING PLANNING SURVEYING 307.637.6017

1103 OLD TOWN LANE, SUITE 101 CHEYENNE, WY 82009 AVI@AVIPC.COM

Dec 14, 2023 DESIGNED BY: CHECKED BY:

JOB NO.:

DRAWING NO. PREPARED DECEMBER 2023

TERRY PARK A PORTION SITUATED IN THE EAST $\frac{1}{2}$ OF SECTION 4 AND A PORTION SITUATED IN THE WEST $\frac{1}{2}$ OF SECTION 3 TOWNSHIP 12 NORTH RANGE 67 WEST OF THE 6TH PRINCIPAL MERIDIAN

ZONE CHANGE

TERRY RANCH BUSINESS

PARK AND A PORTION OF



EXHIBIT B

Purpose: The purpose of the Terry Ranch Business Park PUD is to create an area for commercial and industrial business to develop where the transportation of goods and services is the guiding element and should be cohesive in nature. It also provides the required County improvements to commercial and industrial properties to what is required inside the zone boundary. This PUD cover Terry Park Lot 1, Block 1, and Terry Ranch Business Park Tracts 1-4

- a. Uses by Right
 - i. Restaurant/Food service facilities with or without drive through services
 - ii. Offices
 - iii. Retail, service, and wholesale establishments, with outdoor storage.
 - iv. Any industrial, manufacturing, fabrication, or processing use, associated offices and accessory commercial activities which does not emit noxious noise, smoke, odor, or dust, which does not emit pollutants to the soil and is confined to a building.
 - v. Storage facilities or yards
 - vi. Transportation facilities
 - vii. Warehousing
 - viii. Wholesale uses
 - ix. Bars, cocktail lounges and liquor stores
 - x. Gaming Establishments
 - xi. Hotel
- b. Uses Prohibited
 - i. Mixed-use residential developments
 - ii. Fireworks Sales
 - iii. Adult Entertainment
- c. Maximum Property Coverage

Total building, parking, and outdoor storage area shall not exceed 85 percent of the property area. Best Management Practices for storm water management and open space design is encouraged.

- d. Setbacks
 - i. Buildings
 - a. Front and along all streets 25 feet
 - b. Rear and Side 5 feet
 - ii. Outdoor Display
 - a. 10 feet on all sides

1103 Old Town Lane, Ste 101, Cheyenne, WY 82009



- iii. Outdoor Storage
 - a. Front and along streets 25 feet
 - b. Rear and side 10 feet
- e. Height
 - i. Buildings shall be limited to seventy-five (75) feet in height.
 - ii. Board Approval is required for buildings over seventy-five (75) feet in height.
- f. Parking
 - Parking requirements shall be in conformance with the current Laramie County Land Use regulations.
- g. Commercial Use Site Plan Requirements
 - i. A County-approved site and landscape plan shall be required in accordance with the current Laramie County Land Use Regulations